

J T BEVANN DRYLINING SPECIALISTS LTD

WORKPLACE RISK ASSESSMENT NUMBER: 011				DATE: 30.09.04.		
LOCATION:						
OPERATION/PROCESS MANUAL HANDLING				MANUAL HANDLING ASSESSMENT Will be required for each operative as required.		
EQUIPMENT USED				COSHH ASSESSMENT May be required depending on substance handled		
SUBSTANCES USED Plasterboards/Plasters/Metal/Timber				NOISE ASSESSMENT Depends on background noise		
Hazards Identified				Before Controls		After Controls
				L	M	H
Muscular skeletal injuries if load is too heavy or awkward.						
Operative falling/tripping						
Contamination from substance being carried						
Fall of material being carried						
Exposed Persons: Operatives and bystanders/colleagues						
FREQUENCY OF EXPOSURE Varied				DURATION OF EXPOSURE Varied		
CONTROL MEASURES P.P.E. INSTRUCTION/INFORMATION/TRAINING Operative involved in handling to be assessed on physical capability prior to lifting and carrying. Operative to wear PPE against substance being carried. Ensure good housekeeping against tripping/fall hazards. Operative to get assistance if load too heavy – team lift if necessary. Utilise mechanical lifting and carrying aids where possible. Ensure access equipment, ladders will take weight of operative and load being carried. Ensure item being carried is properly bonded or will not be liable to break apart whilst being manually handled.						
MONITORING RESULTS Manual handling injuries are a constant risk on building sites. Assessment of an operative's training and physical capabilities must be carried out prior to lift.						
ASSESSOR				POSITION		