

J T BEVANN DRYLINING SPECIALISTS LIMITED

METHOD STATEMENT

COMPANY:

LOCATION:

**OPERATION: PLASTERBOARD FIXING
 By Direct Bond (Dot & Dab)
 Tacking to Timber Backgrounds
 Erection of Metal Stud Partitions**

Materials:

- All materials delivered by lorry with either HIAB or Moffatt Mounty Forklift facility.
- Materials unloaded and stacked/stored no higher than 2 pallets in safe manner on level ground within site boundary.
- Loading in carried out in a safe manor to units and stored in a flat and dry condition.

Application:

- The materials to be fixed to the required backgrounds i.e. brick and blockwork, timber joists and rafters and studwork.
- All backgrounds to be checked prior to fixing to make sure of true lines after completion with all sufficient supports being in place.
- Plasterboards to timber will be screw fixed in accordance with Manufacturer's instructions.
- Plasterboards to brick and blockwork will be placed onto plaster dabs at recommended spacing and lined through and plumb with level and straight edges.
- Metal Stud partitions will be set out accordingly to Main Contractor's up-to-date drawings, all in accordance with Manufacturer's recommendations and specification.
- All waste accrued in operations to be disposed of on a regular basis into bags or skips provided by Main Contractor.