

J T BEVANN DRYLINING SPECIALISTS LIMITED

METHOD STATEMENT

COMPANY:

LOCATION:

OPERATION: RENDERING & FLOOR SCREEDING

Materials:

- Sand delivered by tipper lorry and tipped as close to the works as possible.
- Cement delivered on pallets and wrapped to keep dry.
- Wire Mesh delivered in rolls as required.
- All beads delivered in lengths in boxes

Application:

- Screeding – DPM, Thermal Insulation and Acoustic Insulation where specified will be laid to good clean surfaces prior to the mixing of sand and cement for screed finish. The screed will be compacted, ruled level, wood floated and steel trowel finished to required floor level.
- Materials to be barrowed into ground floors of units otherwise the use of screed pump to first floor where required.
- Care will be taken to ensure correct mix as well as good supply of clean water for the mixing of materials.
- Rendering – All beads cut to required length and fixed with either galvanised nails or mortar dabs together with any expanded metal lath and dependant upon background either two or three coat render will be applied. Any scratch coat will be allowed to dry before application of final coat which will be ruled level and finished with either wooden float or steel trowel.
- Care will be taken to ensure correct mix as well as good supply of clean water for the mixing of materials.
- All operatives to wear necessary PPE